# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT27320

## APPROVED SCHEDULE - B

**EE[redacted]TP/BBMP/E-PMT/09/2017-18, Date: 09.10.2017**

**Construction of culverts desilting and Debris Clearance in ward no. 8 Kodigehalli.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of Dhananjaya V | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 2078.23 | KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. | cum | 171.5 | Rupees One Hundred Seventy One and Fifty Paise Only |
| 2 | 8.1 | KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. | cum | 5414.0 | Rupees Five Thousand Four Hundred Fourteen Only |
| 3 | 16.2 | Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6 stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. | cum | 3884.0 | Rupees Three Thousand Eight Hundred Eighty Four Only |
| 4 | 36 | KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications | Sqm | 90.0 | Rupees Ninety Only |
| 5 | 3.24 | KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. | cum | 5047.0 | Rupees Five Thousand Forty Seven Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

12/02

12/02